



IEA PVPS TASK 13 WORKSHOP MUNICH, 30 MAY 2017

Review and Analysis of Technical Assumptions Used in PV Financial Models

Mauricio Richter (3E), Jan Vedde (SiCon),
Mike Green (M.G.Lightning Electrical Engineering),
Ulrike Jahn, Magnus Herz (TÜV Rheinland)



Outline

- Introduction
- Technical Assumptions used in PV Financial Models
 - PV Plant Design
 - Procurement Process
 - Plant Construction
 - Plant Acceptance
 - O&M
- Long-Term Yield Estimates & Their Level of Confidence
- Conclusions



Introduction



- Survey of current practices (questionnaire)
 - 84 PV projects
 - 9 countries
 - Different business concepts
- Complemented with:
 - Results from the Solar Bankability project ^[1]
 - General & public domain industry knowledge

[1] The Solar Bankability project is funded by the European Union's Horizon 2020 research and innovation programme under the grant agreement No 649997.



Technical Assumptions Used in PV Financial Models

Energy flow from sunlight to consumer of electrical power:



Several sub-models
& assumptions
=
Uncertainties



Technical Assumptions Used in PV Financial Models

Weaknesses when dealing with technical assumptions and risks in PV financial models:


PV plant design	Procurement process	Plant construction	Plant acceptance	Operations & Maintenance
<ul style="list-style-type: none"> • Solar Resource • P50/P90 • Degradation behavior • Availability 	<ul style="list-style-type: none"> • Technical specifications • Specific requirements • Factory inspections • Product testing 	<ul style="list-style-type: none"> • Transportation & handling • Storage of components on-site • Construction supervision 	<ul style="list-style-type: none"> • Protocol for visual inspection • Relevant equipment (IR / EL) • Provisional acceptance • Protocol for data collection and KPIs calculation 	<ul style="list-style-type: none"> • Monitoring capabilities • Preventive & corrective maintenance protocols • Relevant equipment (IR / EL)



Weaknesses: PV Plant Design

Solar Resource Assessment

Effect of long-term trends in the solar resource is often not fully accounted for




Forecast of future long-term irradiation based on the average of 32 meteo stations in the Netherlands



Weaknesses: PV Plant Design

Uncertainties calculation

Exceedance probabilities (e.g. P90) are often calculated assuming a normal distribution for all elements contributing to the overall uncertainty



Cumulative distribution function for the long-term (58 years) GHI average of 32 meteo stations in NL



Weaknesses: PV Plant Design

- Incorrect **degradation rate** and inaccurate rendering of the system **behavior over time**
- Incorrect **availability assumptions** used to calculate the initial yield for the project investment financial model as opposed to the O&M plant availability guarantee



Weaknesses: Procurement Process

- **Technical specification** of the PV plant components usually consists only of a high-level description
- Project **specific requirements** such as salt-mist, ammonia or resistance to PID, with the relevant IEC certification testing, are not always specified
- Lack of specifications requiring **factory inspection or product testing**



Weaknesses: Plant Construction

- Absence of standardized **transportation & handling protocol**
- Inadequate quality procedures in component **un-packaging** and handling during construction
- Lack of **construction supervision**



Weaknesses: Plant Acceptance

- Inadequate **protocol for data collection, KPIs calculation and visual inspection**
- Lack of **relevant equipment (IR / EL)**
- No short-term performance test at **provisional acceptance**





Weaknesses: O&M

- Selected **monitoring system** is not capable of **advanced fault detection** and identification
- Missing or inadequate **maintenance of the monitoring system**
- **Preventive & corrective maintenance protocols**
- Inadequate or absent **relevant equipment (IR / EL)**



Long-Term Yield Estimates & Their Level of Confidence


Initial P50 and P90 yield estimates vs actual electricity production for a portfolio of 41 PV plants





Long-Term Yield Estimates & Their Level of Confidence

- Deviations below the confidence margin (P90) disappear after correction
- 1.13% over-estimation (or under-performance?)





Long-Term Yield Estimates & Their Level of Confidence

- Results at **plant level**:
 - For most of the PV plants across the analyzed portfolio the actual electricity production during first year of operation lies **within expected uncertainty ranges**
 - Actual **availability is lower than initial estimates** in LTYA



Long-Term Yield Estimates & Their Level of Confidence

- Results at **portfolio level**:
 - The **yield is slightly lower than initially estimated** during the design phase (-1.15%)
 - The dispersion (**nRMSE**) is **around 4.4%** for the analyzed portfolio
 - These deviations are typically expected to be mainly due to the **variability of the solar resource** and **other site specific losses** that are not precisely modelled during the design phase



Conclusions

- Main areas of weakness in a PV project:
 - **Inaccurate assumptions** for the future behavior of the PV plant
 - Lack of methods to **enable these assumptions** during design, building, commissioning, and O&M
 - **Lack of quality control throughout the plant's life**
- Focus on the technical aspects of the EPC and O&M scopes of work to manage the technical risks linked to the CAPEX and OPEX of PV investments
 - ... **Mitigation measures** (next presentations)



Thank you

Presented by:

Mauricio Richter

MRI@3e.eu